



# टीकापुर नगरपालिका नगर कार्यपालिकाको कार्यालय

फोन नं. { ०९१-५६०४९९  
०९१-५६१२५४  
०९१-५६०११८



प.सं. : २०८२।८३

च.नं. :


## दरभाउपत्र पेश गर्ने सम्बन्धी सूचना

प्रथम पटक प्रकाशित मिति:- २०८३।०१।२४

१. टीकापुर नगरपालिकाको स्वीकृत वार्षिक कार्यक्रम अनुसार तपसिल बमोजिमको कार्य खुला दरभाउपत्र मार्फत गर्नु पर्ने भएकाले ईच्छुक निर्माण व्यवसायीले यो सूचना प्रकाशित भएको मितिले ७ दिन भित्र दरभाउपत्र टीकापुर नगरपालिका, नगर कार्यपालिकाको कार्यालयमा पेश गर्नहुन यो सूचना प्रकाशित गरिएको छ।

क्र.सं.	कामको विवरण	लागत अनुमान रकम	दर-भाउ पेश गर्ने अन्तिम समय	कैफियत
१	शाहिपुर अधुरो बडघर घर को सेफ्टी टंकी, माटो पटानी तथा पेटी निर्माण	३,९९,६५९.३३ (मु.अ.कर समेत)	मिति २०८३।०१।३० (कार्यालय समय भित्र)	

२. दरभाउपत्र पेश गर्ने निर्माण व्यवसायीले अनिवार्य रूपमा दरभाउपत्र पेश गर्ने व्यहोरा सम्बन्धको लिखित निवेदन सहित नविकरण भएको फर्म/कम्पनी दर्ता प्रमाण पत्रको प्रतिलिपी, मु.अ.कर दर्ता प्रमाण पत्रको प्रतिलिपी, नविकरण भएको निर्माण व्यवसायी ईजाजतपत्रको प्रतिलिपी, चालु आ.व.को लागी टीकापुर नगरपालिकामा सुचिकृत भएको निस्साको प्रतिलिपी र आ.व. २०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपी संलग्न गरी पेश गर्नुपर्ने छ।
३. उक्त कार्यको लागि आवश्यक BOQ यस कार्यालयको वेबसाइट <http://www.tikapurmun.gov.np> बाट डाउनलोड गर्न सकिनेछ।
४. BOQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरी लेखेर पेश गर्नु पर्नेछ। केरमेट भएको दरभाउपत्र (BOQ) मुल्याङ्कनमा समावेश गरिने छैन।
५. प्रस्तावदाताहरूले दरभाउपत्र सार्वजनिक खरिद नियमावली, २०६४ को नियम ८५ को उपनियम १(ख) बमोजिम उल्लेखित सिमा (दश लाख) भित्र रही पेश गर्नु पर्नेछ।
६. दरभाउपत्र पेश गर्ने अन्तिम दिन सार्वजनिक विदा पर्न गएमा सो दिनको भोली पल्ट कार्यालय समयभित्र दरभाउपत्र पेश गर्न सकिनेछ।
७. म्याद नाधी आएको, रित नपुगेको वा कुनै शर्त राखी पेश गरेको दरभाउपत्र मान्य हुने छैन।
८. माथि उल्लेखित बाहेक प्रचलित ऐन कानुन बमोजिम हुनेछ।

  
राजेन्द्र रावल

नि.प्रमुख प्रशासकीय अधिकृत

नि.प्रमुख प्रशासकीय अधिकृत

वेबसाईट : [www.tikapurmun.gov.np](http://www.tikapurmun.gov.np)

सम्पर्क नं. : सा.प्रशासन शाखा ०९१- ५६०८१६

श.पु.तथा वि.शाखा ०९१- ५६१३२५

ईमेल : [tikapurmun@gmail.com](mailto:tikapurmun@gmail.com)

सा.ख.तथा स.व्य.उपशाखा ०९१- ५६०८८३

वारुणयन्त्र ०९१-५६०४९९

TIKAPUR MUNICIPALITY  
OFFICE OF MUNICIPAL EXECUTIVE  
SUDURPASHIM PROVINCE  
TIKAPUR, KAILALI

NAME :- PROJECT :- शाहपुर अघुरो बढघर घरको सेप्टिक टंकी, माटो पाटानी तथा पेटी निर्माण योजना  
LOCATION :- टिकापुर नगरपालिका -०५, शाहपुर

FISCAL YEAR :- 2082/083



*(Signature)*  
प्रमुख प्रशासकीय अधिकृत

**BILL OF QUANTITY**

S.No.	DESCRIPTION	QUANTITY	UNIT	RATE EXCLUDING VAT		AMOUNT	REMARKS
				IN FIGURE	IN WORDS		
A	PROVISIONAL SUM						
1.00	SUPPLY AND INSTALL PROJECT INFORMATION BOARD	1.00	PS			4000.00	
A	CIVIL WORKS						
2.00	EARTHWORK IN EXCAVATION IN TRENCHES, FOUNDATION ETC. IN SOFT SOIL INCLUDING TYPING AND PUMPING OUT WATER FROM THE BASEMENT (IF NECESSARY) DRESSING SIDES, RAMMING OF BOTTOM, LIFT UPTO 3.5M, AS PER SPECIFICATION, DRAWINGS & INSTRUCTION OF SITE ENGINEER.	23.95	M3				
3.00	STONE SOILING WORK WITH SAND FILLING. ALL COMPLETE WORK AS PER DRAWINGS, SPECIFICATIONS AND INSTRUCTION OF THE SITE ENGINEER.	3.13	M3				
4.00	FORMING, LAYING, COMPACTING AND CURING PLAIN CEMENT CONCRETE M10 (1:3:6) IN FOUNDATION WITH CEMENT, SAND AND STONE BALLAST 20MM GAUGE FINISHING TO APPROVED LEVEL, LINES AND DIMENSIONS ALL COMPLETE AS PER DRAWINGS, SPECIFICATIONS AND INSTRUCTION OF THE SITE ENGINEER.	1.57	M3				

TIKAPUR MUNICIPALITY  
OFFICE OF MUNICIPAL EXECUTIVE

SUDURPASHIM PROVINCE  
TIKAPUR, KAILALI

NAME OF PROJECT: *अधुनो बढ्दघर घरको सेप्टिक टंकी, माटो पाटानी तथा पेटी निर्माण योजना*

LOCATION :- टिकापुर नगरपालिका -०५, शाहिपुर

FISCAL YEAR :- 2082/083

प्रमुख प्रशासकीय अधिकृत



BILL OF QUANTITY

S.No.	DESCRIPTION	QUANTITY	UNIT	RATE EXCLUDING VAT		AMOUNT	REMARKS
				IN FIGURE	IN WORDS		
5.00	FIRST CLASS CHIMNEY MADE BRICK WORK (1:4) IN SUB - STRUCTURE & SUPERSTRUCTURE IN GROUND FLOOR IN CEMENT SAND MORTAR WITH APPROVED QUALITY BRICKS IN PERFECT LINE & LEVEL UPTO PLINTH LEVEL INCLUDING WETTING THE BRICKS, PROPERLY PACKING THE JOINTS & CURING THE WORKS WITH ALL COMPLETE AS PER INSTRUCTION OF SITE INCHARGE/ ENGINEER ON THE BASIS OF DRAWINGS, SPECIFICATIONS ETC	17.02	M3				
6.00	PCC FOR RCC WORKS : PROVIDING, LAYING, COMPACTING AND CURING M20 (1:1.5:3 ) PLAIN CEMENT CONCRETE FOR SLAB, COLUMNS, BEAMS, TIE BEAM LINTEL SILL FINS AND ALL KINDS OF R.C.C. WORKS WITH CEMENT SAND AND CRUSHED AGGREGATE OF REQUIRED SIZE FINISHING TO APPROVED LEVEL, LINE AND DIMENSIONS ALL COMPLETE USING CONCRETE MIXTURE AND COMPACTION WITH VIBRATOR INCLUDING FORMWORKS AS PER SPECIFICATIONS, DRAWINGS AND INSTRUCTIONS OF THE SITE ENGINEER, ALL COMPLETE:	0.11	M2				

TIKAPUR MUNICIPALITY  
OFFICE OF MUNICIPAL EXECUTIVE  
SUDURPASHIM PROVINCE  
TIKAPUR, KAILALI

प्रमुख प्रशासकीय अधिकृत



NAME OF PROJECT :- शाहिपुर ~~इंजिनियर~~ बढघर घरको सेप्टिक टंकी, माटो पाटानी तथा पेटी निर्माण योजना

LOCATION :- टिकापुर नगरपालिका -०५, शाहिपुर

FISCAL YEAR :- 2082/083

**BILL OF QUANTITY**

S.No.	DESCRIPTION	QUANTITY	UNIT	RATE EXCLUDING VAT		AMOUNT	REMARKS
				IN FIGURE	IN WORDS		
7.00	TORSTEEL STEEL BARS (GRADE 500) REINFORCEMENT WORK INCLUDING STRAIGHTENING, CLEANING, CUTTING, BENDING, BINDING WITH 20 SWG ANNEALED WIRE & FIXING IN POSITION AS PER DRAWING, BAR BENDING SCHEDULE FOR RAFT FOUNDATION COLUMN, BEAM, WALL, STAIR, SLAB IN ALL R.C.C. WORKS AS PER SPECIFICATION, DRAWING & INSTRUCTION OF SITE ENGINEER. APPROVED BRANDS: HIMAL IRON, PANCHAKANYA OR EQUIVALENT.	97.30	KG				
8.00	12.5 MM PLASTER WORK IN 1:4 C/S MORTAR ALL COMPLETE WORK AS PER DRAWINGS, SPECIFICATIONS AND INSTRUCTION OF THE SITE ENGINEER.	62.43	KG				
9.00	3 MM PUNNING WORKS ALL COMPLETE WORK AS PER DRAWINGS, SPECIFICATIONS AND INSTRUCTION OF THE SITE ENGINEER.	55.00	KG				
10.00	EARTHWORK IN FILLING IN LAWN INCLUDING CONSOLIDATION IN LAYERS OF 15 CM AND WATERING AS PER INSTRUCTION OF SITE ENGINEER.	30.75	M3				
SUB-TOTAL							
VAT 13%							
GRAND TOTAL							
IN WORDS:							

COMPANY'S NAME:-  
NAME OF CONTRACTOR :-  
ADDRESS :-  
PHONE NO :-  
DATE :-

COMPANY'S SEAL :-  
CONTRACTOR'S SIGNATURE :-  
MOBILE :-  
FAX :-  
E-MAIL :-